



- REQUIREMENTS FOR CONCRETE COLLARS:
1. CONCRETE : 3/4", 7 SACK, 4000 PSI@ 28 DAYS, 2" TO 4" SLUMP, 4-7% AIR.
 2. COLLAR TO BE FORMED AND UNIFORMLY ROUND.
 3. SMOOTH BROOMED FINISH REQ'D.
 4. APPLY CONCRETE CURING COMPOUND.
 5. PROTECT FROM TRAFFIC FOR 4 DAYS MIN.

VALVE CONCRETE COLLAR DETAIL
IN ASPHALT STREETS, GRAVEL STREETS, OR NATURAL GROUND
 N.T.S.

REVISION	DATE
GENERAL UPDATES	12/06

**CITY OF
UNION
OREGON**

STANDARD WATER DETAILS
 VALVE CONCRETE COLLAR DETAIL

FIGURE
W6